Greenbow Construction Co.

www.example.com

ESTIMATE

Job: Oak Hill Farm Shop

Job no. J-0003

Date: September 30, 2026

Customer	Sample Customer
Company	Oak Hill Farm Shop
Phone	(555) 010-0199
Email	sample.customer@example.com
Job site	Anytown, AL
Prepared by	Jordan Avery · jordan.avery@example.com



Computer-generated picture — an approximation of the building.

Colors

	Roof	Walls	Trim	Wainscot
Structure 1	Burnished Slate	Light Stone	Burnished Slate	Burnished Slate
Structure 2	Burnished Slate	—	Burnished Slate	—

Building details

Structure 1 — Main building: 40'-0" × 60'-0" × 14'-0" (2,400 sq ft) enclosed gable, 4/12 pitch.

(1) 12' x 12' Roll-up Door w/ chain hoist (Polar White) — Endwall A
(1) 3070 Double Lock, half glass w/frame — Endwall A
(1) 12' x 12' Roll-up Door w/ chain hoist (Polar White) — Endwall B
(1) 3070 Double Lock w/ frame — Endwall B
(1) 10' x 10' Roll-up Door w/ chain hoist (Polar White) — Sidewall A
(2) 3'-0" × 4'-0" framed window opening (window by others) — Sidewall B
(1) 3070 Double Lock w/ frame — Sidewall B
Clear Span frame (Red Oxide)
Secondary framing: Red Oxide
PBR Panel roof and walls
3'-0" wainscot on all walls
Concrete Slab, 4" (2,400 sq ft)

Structure 2 — Lean-to, Sidewall A: 12'-0" × 60'-0" × 12'-0" (720 sq ft) open, 2/12 pitch.

Eaves: 14'-0" at the building, 12'-0" at the outer edge
PBR Panel roof
Concrete Slab, 4" (720 sq ft)

Estimated price: $ • • • – $ • • •

Jordan Avery

Prepared by

SAMPLE · prices hidden · raftersuite.com

This estimate is valid for 10 calendar days from the date above.

The picture is a computer-generated approximation. The building details above describe what is included; please direct any questions to your Greenbow Construction Co. representative.

Any change to the building requires a new estimate and a work authorization signed by both parties.

Sales tax is not included.

Delivery (freight) is not included.

SAMPLE